

WESTREC MARINA MANAGEMENT, INC.  
ON BEHALF OF THE CHICAGO PARK DISTRICT

---

---

**INVITATION FOR BID (IFB)  
FOR  
CONSTRUCTION OF DOCK GATES**


---

---

W-19001

**ADDENDUM 1**

**BID DUE DATE: Monday, February 4, 2019, at 3 P.M. C.S.T.**



## Answers to Submitted Questions

- Q. Is the awardee responsible for demolition and removal of the existing gates?
- A. Yes. However, Westrec may elect at its discretion to retain some of the existing gates or gate parts. Westrec will remove and retain all light globes from Burnham gates and all combination locks from existing gates.
- Q. Does the completion of installation and full operation of all gates by April 20, 2019 include the access system?
- A. Yes. Contractor is responsible for scheduling with the electrical contractor, Evans Electrical, and access system contractor, Amano McGann, in order to meet this date. Contact information for both contractors is as follows:
- Amano McGann
    - Contact: Matt Librizzi
    - Phone: 312.491.8325
    - Email: [Matt.Librizzi@amanomcgann.com](mailto:Matt.Librizzi@amanomcgann.com)
  - Evans Electric
    - Contact: Andy Carbonaro
    - Phone: 708.878.9633
    - Email: [andyc@evanselec.com](mailto:andyc@evanselec.com)
- Q. Is the awardee responsible for security to the dock when the old gates are removed?
- A. No. The awardee is only responsible for normal workplace safety and security.
- Q. Does the awardee have to provide for temporary gates after removal of the existing gates?
- A. No.
- Q. Does the awardee have to install the lights on the gates?
- A. Yes, the awardee must mount the lights per manufacturer's specifications, but wiring will be done by the electrical contractor.
- Q. Where is the floating bathroom at Burnham positioned?
- A. Adjacent to north side of P dock as shown on diagram on page 2.
- Q. Will all pieces of new gates be powder coated? Print detail calls for some to be galvanized?
- A. Yes, all panels and posts to be powder coated.
- Q. On the 2 extended wing pieces, do you want to add the expanded metal on top of grate? This is on new style gates installed now.
- A. No, you do not need to add any expanded metal on top of the gate.
- Q. Other than the gate, are all the other parts (camera, light, keypad, magnetic lock, etc.) to be supplied by others?
- A. Camera, keypad and exit switch are provided by Amano McGann. NEMA enclosures are provided by Evans Electric. Light and magnetic lock are provided by awardee. Awardee will work with contractors to ensure proper mounting points, holes for wiring runs and equipment mounting are pre-fabricated for installation.

